



Install wire backed silt fencing on all downslopes and across all lot frontages.

All erosion control measures must be maintained for the duration of construction.

No parking or material storage is allowed on grass mat or undisturbed vegetation.

The **REQUIRED** construction sign must not be larger than 3 square feet and shall include at a minimum:
CONSTRUCTION SITE--NO TRESPASSING
PHYSICAL ADDRESS
CONTRACTOR NAME W/ 24HR EMERGENCY CONTACT #
QCP NAME W/ 24HR EMERGENCY CONTACT #

As shown is minimum required.

Contractor is required to install and maintain adequate measures to keep siltation from leaving the site.

Contractor must provide the City with a written inspection and action report on a weekly basis and after each rainfall event.